

EXTERIOR REPAINT PROPOSAL • JULY 13, 2026

Alhambra Village No 1

A full exterior repaint of all seven residential buildings and the pool house — 55 units at 4551 Castlepalm Road, Orlando — built to the Sherwin-Williams specification and priced to hold.



Color rendering — Sherwin-Williams color study 26-03-2773, Scheme 1. Final colors selected by the Association.

PREPARED FOR

Yvonne Kamara, LCAM

Soaring Management
Alhambra Village 1 Condominium Association
4551 Castlepalm Road, Orlando, FL 32839

PRESENTED BY

Jordan Schiller

Affordable Quality Painting
407-982-0508 • Jordan@aqpaintingco.com
aqpaintingco.com

One painting partner. Zero fire drills.

You're accountable for the budget, the schedule, and a board that expects both — the last thing you need is a vendor you have to chase. AQP is a Florida Certified General Contractor running exclusive in-house crews, with a dedicated project manager on every job and a number that won't move. This proposal is built to be forwarded straight to your board.

Most managers end up babysitting painting vendors and explaining blown budgets to ownership. With AQP, the project quietly lands on time and on budget — so you become the manager your board relies on.

The AQP Standard — six promises on every project

Certified General Contractor

CGC1540185. Licensed to handle the repairs most painters can't touch — stucco, wood, and structural work under one roof.

No change orders, ever

The number we quote is the number you pay. Any additional work happens only at the published rates in this proposal, with your written approval.

Dedicated project manager

One point of contact. Weekly site reports, resident notices coordinated with your office, and a reply within 3 hours.

Full-time QC supervisor

Three-stage punch-out. Crew, then our QC supervisor, then you — the finish is right before you ever walk it.

Exclusive in-house crews

No outside subcontractors. Our own crews work occupied communities every day — no subcontractor markups, no strangers on site.

Proven systems

Specified, not guessed. Sherwin-Williams systems matched to your substrates and applied at proper mil thickness — verified as we go.

250+

COMMUNITIES
COMPLETED

3 / 10

YR LABOR /
PRODUCT
WARRANTY

\$1M/\$2M

GENERAL LIABILITY

\$5M

EXCESS LIABILITY

\$1M

WORKERS' COMP

YOU'RE IN GOOD COMPANY — MANAGEMENT & OWNERSHIP GROUPS THAT TRUST AQP

SENTRY • SIMON • ZRS • COHEN • TRIGILD • HIGHMARK

Scope of work

A complete exterior repaint of the community, executed to Sherwin-Williams specification 26-03-2773 and painted to full coverage — surface preparation, repair, priming, and finish coats on every previously painted substrate.

The buildings

STRUCTURE	WALL SF EACH	QTY	TOTAL SF
Building Style 1	15,400	3	46,200
Building Style 2	11,000	2	22,000
Building Style 3	8,800	2	17,600
Pool House	4,400	1	4,400
Total — 55 units		8	90,200

What's included

Pressure wash. Complete wash of all buildings with chlorine treatment to kill mold, mildew, and algae at the root — vulnerable plants covered.

Crack repair & patching. Hairline and up to 3/8" stucco cracks routed, cleaned, and sealed with elastomeric patching compound per spec.

Caulking. Underperforming sealants removed and replaced with Sher-Max / Loxon H1 at joints, windows, and penetrations.

Full prime. Loxon Conditioner bonding coat on all walls; bare or high-pH masonry spot-primed with Loxon Masonry Primer.

Finish coats. Latitude Exterior Acrylic Satin applied to full coverage — stucco walls, previously painted wood siding, soffit & fascia.

Entry doors. Degreased, sanded, primed with Pro-Cryl, and finished in Pro Industrial Waterbased Alkyd Urethane enamel.

Metal railings. Rust removed to sound metal, primed with Kem Kromik, and finished in WB Alkyd Urethane.

Corner beads & details. Exposed rusted corner beads treated and spot-primed per spec; electrical boxes and previously painted fixtures coated.

Protection & cleanup. Windows, walkways, and landscaping protected daily; overspray removed; the site left clean every evening.

Landscaping guarantee. Any landscaping loss during the project is covered by AQP.

Colors. The Association selects from the three Sherwin-Williams color studies (Schemes 1–3). Before full production, we paint on-site samples so the board approves the real thing — not a screen.

Factory-finished gutters & downspouts are omitted per the specification — we're happy to price them on request.

THE NUMBER

Your investment

One number for the complete repaint — all labor, materials, equipment, supervision, and site protection. It includes everything on the scope page, and it won't move.

FULL EXTERIOR REPAINT — COMPLETE

\$81,273

Seven residential buildings + pool house · 55 units · 90,200 SF

\$0.90 per square foot

\$1,478 per unit

5-6 weeks on site

Backed by our 3-Year Labor & 10-Year Product Warranty

Payment schedule

MILESTONE	SHARE	AMOUNT
Mobilization	30%	\$24,382
Final — after joint walk-through & punch-out	70%	\$56,891

Nothing else is due while the work is in progress — no monthly invoices to process, no draw requests to chase.

Schedule

We estimate 5-6 weeks on site, sequenced building-by-building so residents always know what's next. Resident notices are drafted and timed with your office before each phase, and your project manager sends a written site report every week.

This price is held through December 31, 2026. Approve any time this year and the number stays exactly as written — no re-quotes, no escalation clauses.

If we find wood rot or damaged stucco

Hidden damage sometimes shows itself once pressure washing strips away old coatings. Most contractors price that moment as leverage — we publish our rates up front, so your board already knows exactly what repairs cost.

Stucco repair

REPAIR TYPE	WHAT IT COVERS	RATE
Type 1 — Surface	Remove damaged stucco; install new vapor barrier and lath; apply new stucco matched to the existing finish. No wood replacement required.	\$36 / SF
Type 2 — Structural	Everything in Type 1, plus replacement of deteriorated wood or framing members behind the stucco before the new finish goes on.	\$62 / SF

Wood rot repair & replacement — pressure-treated pine

BOARD DIMENSION	TYPICAL USE	RATE
1×4	Trim, battens	\$8 / LF
1×6	Trim, fascia	\$9 / LF
1×8	Fascia	\$10 / LF
2×4	Framing, blocking	\$10 / LF
2×6	Framing, rafter tails	\$12 / LF
2×8	Framing, headers	\$14 / LF
Plywood — ½" or ¾"	Sheathing, decking	\$8 / SF

All replacements are pressure-treated pine, fastened, sealed, and painted to match. Other dimensions are quoted from the same published price list.

How additional work is handled

STEP 1

Document

We photograph and measure every affected area and send it to you the same day.

STEP 2

Approve

You approve exact quantities in writing at the rates on this page — nothing starts without it.

STEP 3

Complete

Repairs are finished and painted within the project schedule — no return trips, no re-mobilization fees.

No surprises, by design. These are the same rates we publish for every community we serve — approved quantities are the only variable, and \$0 of additional work is billed without your signature.

WHAT TO EXPECT

Service without disruptions

Every disruption on the property lands on your desk as a complaint. Our in-house crews work occupied communities every day — clear notices, clean sites, and a dedicated project manager coordinating the whole thing so your residents barely notice the work.

STEP 1

Coordinate

We plan the sequence around your residents and handle the notices with your office — parking, walkways, and pets all accounted for.

STEP 2

Execute clean

Low-disruption work on your schedule. Tidy sites every evening, weekly written reports, and a reply from your PM within 3 hours.

STEP 3

Walk & turn

Three-stage punch-out — crew, then our QC supervisor, then you. We walk the finished work together before we call it done.

What other communities say

"We have received only positive feedback from our residents, both for their professionalism and quality of work. I can confidently recommend Affordable Quality Painting as a solid and dependable company that provides exceptional service."

**KIM MORRISON • PROPERTY MANAGER,
MIDDLEBROOK FARMS**

"We were so satisfied with the work that was done by AQP that we hired them for additional work, such as fencing and decking, and will continue to bring them on for future work."

**ASSOCIATION MANAGEMENT TEAM • SERENATA
CONDOMINIUMS**

Before & after — your community



Today — existing finish



Rendered — SW Scheme 1 (Association selects final colors)

Approve & schedule

To move forward, sign below — or simply reply to Jordan@aqpaintingco.com. We'll schedule the board's on-site color samples and lock in your start window.

Terms of this proposal

- **Price.** \$81,273 for the full exterior repaint as scoped on page 3, held through **December 31, 2026**. Payment per the schedule on page 4.
- **Warranty.** 3-year labor warranty on all AQP work; 10-year Sherwin-Williams product warranty. Work performed to Sherwin-Williams specification 26-03-2773 and manufacturer data sheets to preserve product warranty coverage.
- **Additional work.** Wood rot and stucco repairs are performed only with the Association's written approval, at the published rates on page 5. No other charges of any kind.
- **Insurance.** Certificates furnished on request — General Liability \$1M/\$2M, Excess Liability \$5M, Workers' Compensation \$1M, Automobile \$1M. Additional coverages added quickly if required.
- **Licensing.** Affordable Quality Painting is a Florida Certified General Contractor, license CGC1540185.
- **Site.** Association provides water and electricity from existing facilities. AQP maintains OSHA-compliant signage and work-area protection; landscaping loss is covered by AQP.

Acceptance

Signature — Alhambra Village 1 Condominium Association /
Soaring Management

Date

Printed name & title

Board approval date (if
applicable)

AQP | AFFORDABLE
QUALITY PAINTING

Jordan Schiller

407-982-0508 · Jordan@aqpaintingco.com
aqpaintingco.com · CGC1540185